



PAMBANSANG MUSEO NG PILIPINAS
NATIONAL MUSEUM OF THE PHILIPPINES

BID BULLETIN NO. 2023 – 01

Project Title : Exhibitions and fit-out of various National Museum of the Philippines Central and Regional Sites (Replacement of Defective Air-Conditioning Units at NMFA Building)

Item No. 1 : Clarifications; LOT 1

1. The power supply for all air-conditioning units to be supplies, delivered and installed is 230V / 3Phase / 60Hz
2. The existing pipe lines (copper tube & drain pipe) shall be used for the new air-conditioning units. Flushing of pipe lines shall be shouldered by the Contractor.
3. If there is a requirement for additional or upgrade of copper tube & drain pipe, it will be shouldered by NMP

Item No. 2 : Revision on the Section VII. Technical Specifications and Annex C Technical Specifications; LOT 1

Original	Revised
4TR Inverter Ceiling Cassette Air-conditioning Units – 6 units	5TR Inverter Ceiling Cassette Air-conditioning Units – 6 units

Item No. 3 : Revision on the Section VII. Technical Specifications and Annex C Technical Specifications; LOT 2

Original	Revised
Cooling capacity: 5,000BTU/H minimum	Cooling capacity: at least 18,000 kJ/h

Item No. 4 : Revision on the Section VII. Technical Specifications and Annex C
Technical Specifications; LOT 2

BIDDER'S QUALIFICATIONS

Original	Revised
1. Engaged in with the same business for at least two (2) years or more)	1. Engaged in with the same business for at least two (2) years or more)
2. Prospective Bidder's office must be within Metro Manila.	


Done this 22th day of August 2023.

Prepared by:



EDWIN J. DELA ROSA
Head, BAC Secretariat

Approved by:


ATTY. MA. ROSENNE M. FLORES-AVILA
Chairperson
Bids and Awards Committee

ENCL: NONE
CC: NONE
BACSEC/DELA ROSA/NLV